BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT44678

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/06/2020-21, Date: 03-09-2020

Name of Work:Improvements to Roads and drains at Gupta Vidyasagar layout and surrounding area roads in ward no 06 Thanisandra

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M L DHANANJAYA ( )	
				In Figures	In Words
1	729.66	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods Complete as per specifications and directions of the Engineer in charge. 5km lead= 57+2.0x1.28x5 =69.80	Cum	217.96	Rupees Two Hundred Seventeen and Ninety Six Paise Only
2	9.86	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing Complete as per specifications and directions of the Engineer in charge	Cum	5184.18	Rupees Five Thousand One Hundred Eighty Four and Eighteen Paise Only
3	437.41	Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days Including cost of materials,labour, HOM curing form work, Scaffolding and Centering omplete as per specifications and directions of the Engineer in charge.	Cum	5692.45	Rupees Five Thousand Six Hundred Ninety Two and Forty Five Paise Only
4	0.91	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)	Cum	6034.11	Rupees Six Thousand Thirty Four and Eleven Paise Only
5	234.11	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM Complete as per specifications and directions of the Engineer in charge.	Cum	7423.0	Rupees Seven Thousand Four Hundred Twenty Three Only
6	14.15	Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery omplete as per specifications and directions of the Engineer in charge.	tonne	68292.74	Rupees Sixty Eight Thousand Two Hundred Ninety Two and Seventy Four Paise Only
7	487.71	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,omplete as per specifications and directions of the Engineer in charge.(Data Rate)	Sqm	2453.62	Rupees Two Thousand Four Hundred Fifty Three and Sixty Two Paise Only
8	34.44	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,Complete as per specifications and directions of the Engineer	Sqm	5688.36	Rupees Five Thousand Six Hundred Eighty Eight and Thirty Six
9	990.3	Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and Complete as per specifications and directions of the Engineer in charge.	Cum	59.07	Rupees Fifty Nine and Seven Paise Only
10	2200.67	Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM Complete as per specifications and directions of the Engineer in charge.	Sqm	6.68	Rupees Six and Sixty Eight Paise Only

Signature of the contractor

10/12

Executive Engineer

10/12

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M L DHANANJAYA ( )	
				In Figures	In Words
11	330.1	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density,Complete as per specifications and directions of the Engineer in charge.	Cum	2094.47	Rupees Two Thousand Ninety Four and Forty Seven Paise Only
12	330.1	Cement concrete pavement.Construction of un-reinforced plain cement concrete for pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008.mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire charges of machineries,all lead and lift charges etc., Complete as per specifications and directions of the Engineer in charge.	Cum	5470.99	Rupees Five Thousand Four Hundred Seventy and Ninety Nine Paise Only

M. Dhananjaya
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
10/12

10/12